

GENERAL NOTES FOR EROSION AND SEDIMENT CONTROL

- 1) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE SITED, DESIGNED, CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE WASHINGTON STATE DEPARTMENT OF ECOLOGY STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON.

- 2) **PRIOR TO ANY LAND DISTURBING ACTIVITY:**
 - CLEARING AND WORK AREA LIMITS SHALL BE CLEARLY DELINEATED AND MARKED. ALL SENSITIVE OR CRITICAL AREAS (WETLANDS, STEEP SLOPES, WATERWAYS, TREES TO BE PRESERVED, ETC.) AND THEIR BUFFERS SHALL BE CLEARLY MARKED AND PROTECTED WITH APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES.

 - ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE, IN WORKING CONDITION AND INSPECTED & APPROVED BY CDID1. ADDITIONAL MEASURES MAY BE REQUIRED AS CONSTRUCTION PROGRESSES AND/OR SEASONAL CONDITIONS DICTATE.

 - A CONSTRUCTION ENTRANCE SHALL BE ESTABLISHED TO MINIMIZE TRACKING SEDIMENT. ANY SEDIMENT OR DEBRIS TRACKED ONTO ROADWAYS OR SIDEWALKS SHALL BE REMOVED IMMEDIATELY BY SHOVELING AND/OR SWEEPING.

 - ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REGULARLY INSPECTED AND MAINTAINED THROUGHOUT THE DURATION OF THE PROJECT. INSPECTIONS SHALL OCCUR DAILY ON ACTIVE SITES, WEEKLY ON INACTIVE SITES AND WITHIN 24-HOURS FOLLOWING A 0.5 INCH OR GREATER RAIN EVENT. THE CONTRACTOR SHALL MAINTAIN A LOG OF SAID INSPECTIONS AND MAINTENANCE AND PROVIDE A 24-HOUR CONTACT NUMBER FOR EMERGENCY MAINTENANCE AND REPAIR OF SITE MEASURES.

 - STORM DRAIN INLETS WITHIN OR DOWN SLOPE OF THE PROJECT AREA SHALL BE PROTECTED. INLET PROTECTION SHALL BE CLEANED OR REPLACED AS NEEDED TO MAINTAIN DRAINAGE AND ENSURE PERFORMANCE. ALL INLET PROTECTION SHALL BE REMOVED PROMPTLY UPON COMPLETION OF THE PROJECT.

- 3) TO THE MAXIMUM EXTENT PRACTICABLE, MINIMIZE THE DISTURBANCE OF NATURAL VEGETATION, SOILS AND SLOPES.

- 4) STOCK PILES SHALL BE STABILIZED AND LOCATED AWAY FROM STORM DRAIN INLETS, DRAINAGE DITCHES AND WATERWAYS.

- 5) SEDIMENT SHALL NOT BE ALLOWED TO ENTER NEW OR EXISTING STORMWATER FACILITIES OR DRAINAGE DITCHES. IF THIS OCCURS, THE CONTRACTOR SHALL REMOVE ALL ACCUMULATED SEDIMENT AND MAKE APPROPRIATE REPAIRS.

- 6) STRAW MULCH USED FOR TEMPORARY EROSION CONTROL SHALL BE CERTIFIED WEED FREE. SEED MIX SHALL BE A PERENNIAL RYE & FESCUE BLEND.

- 7) DURING DRY WEATHER CONSTRUCTION PERIODS, DUST CONTROL MEASURES SHALL BE IMPLEMENTED UNTIL ALL DISTURBED AREAS ARE STABILIZED.

- 8) DISTURBED AREAS NOT BROUGHT TO FINAL GRADE OR GIVEN PERMANENT COVER WITHIN 30 DAYS OF EXPOSURE SHALL BE TEMPORARILY SEEDED AT A MINIMUM RATE OF 180 LBS/ACRE OR MULCHED TO STABILIZE THE SOIL.

- 9) ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER SITE STABILIZATION IS ACHIEVED. CONSTRUCTION SHALL NOT BE CONSIDERED COMPLETE UNTIL ALL DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.



	TC	ANB	ANB	ANB	ANB	ANB	ANB
new standard							
7/2020							
	REV					DWG	DES
						CHK	APP
						ISSUE	

EROSION CONTROL GENERAL NOTES DETAIL

DATE: JULY 2020
 DESIGN: ANB
 DRAWN: TC

DRAWING NO.
EC-1
 1 of 1